

CHITALDRUG DIVISION.

Notification dated 29th April 1939.

1. Sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 2 P.M., on 22nd May 1939, for constructing a new tank at Mettikurke, Hiriur Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Chitaldrug Division, should be addressed to the Executive Engineer, Chitaldrug Division, in a sealed cover and superscribed as "Tender for constructing a new tank at Mettikurke, Hiriur Taluk." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a deposit of Rs. 1,000 (Rupees one thousand only) in cash or Government Promissory Notes or Mysore Government Bonds, duly endorsed at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract. Such a deposit in cash will not carry any interest. The balance of the earnest money should be paid after acceptance of the tender.

4. The tenders will be opened in the presence of such tenderers, as wish to be present on 22nd May 1939 at 4 P.M. The final acceptance of the tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the Departmental Schedule Contract Form, for the due fulfilment of the contract, and for the execution of all items of work in accordance, with the Bombay specifications (1931).

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force, will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of tender notification, contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Chitaldrug, on all working days, between 11 A.M. and 5 P.M. and may be obtained from that officer on payment of Re. 1.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The work should be completed and handed over in a tidy condition to the Public Works Department by the end of June 1942, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 50 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(a) The contractor should at his own cost—

- (1) Provide rods, stakes, ropes and labour required in setting out the works.
- (2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
- (3) Provide mortar mills and sheds to keep materials under cover and also for workmen.
- (4) Arrange for protecting work during inclement weather.
- (5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
- (6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
- (7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
- (8) Provide arrangements for pumping and baling of water from excavations and foundations, wherever and whenever necessary with his own pumping apparatus, including necessary leading drains, slump pits, etc.
- (9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract and give such persons the use of ordinary scaffolding and ladders.
- (10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary, provide for the same by insurance at the proper time.

(b) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

23. For lumpsum provisions in the estimate, no lumpsum amounts will be paid but actual quantities will be recovered and paid. The contractor may quote for all the probable items of work.

24. Chamundi Brand cement alone have to be used.

Abstract estimate for constructing a new tank at Mattukurki, Hiriyr Taluk.

Sl. No.	Details of work	Unit	Rate	Quantity	Rates tendered	
					In words	In figures
	<i>Bund.</i>		Rs. a. p.			
1	Earthwork excavation for revetment and gravel backing	C.yd.	0 3 0	5,703		
2	Using the excavated earth to bund including watering and consolidation	"	0 1 6	5,703		
3	Removing wet silt clayey	"	0 3 0	11,260		
4	Puddle core wall	"	0 8 0	1,398		
5	Earthwork to bund including watering and consolidation	"	0 5 0	61,931		
6	Rough stone revetment with jelly backing	"	1 8 0	5,702		
7	Gravel backing including watering and consolidating	"	0 8 0	2,544		
8	Turfing	Sqrs.	0 10 0	956		
9	Register number stone	Each	5 0 0	1		
10	Gauge stone	"	15 0 0	1		
11	B. M. Number stones	"	2 8 0	2		
12	Grade stones	"	2 4 0	28		
13	Top width or index stones	"	1 6 0	28		

Sl. No.	Details of work	Unit	Rate	Quantity	Rates tendered	
					In words	In figures
			Rs. a. p.			
14	Clearing Jungle		L. S. as per actual measurements.			
15	Cutting steps at the ends of hallas		Do			
16	Sundry and unforeseen					
	<i>Sluice No. 1 R.L. 46.00.</i>					
1	Earthwork excavation	C.yd.	0 3 0	46		
2	Concrete in surki mortar	C.ft.	0 4 0	310		
3	Size stone in surki mortar	C.ft.	0 5 0	1,062		
4	Cement concrete slab 6" thick	"	0 10 0	42		
5	Fixing 16" diameter C.I. pipes including carting, etc.	Cwt.	8 0 0	50		
6	Providing plug and rod including locking arrangements					
7	Cement pointing	Sqr.	4 0 0	4.50		
8	Cutting holes in orifice slab	Each				
9	Sundry and unforeseen charges		As per actual measurements.			
	<i>Sluice No. 2 at 48.00.</i>					
1	Earthwork excavation					
2	Concrete in surki mortar	C.ft.	0 4 0	260		
3	Burnt stone in surki mortar	"	0 5 0	879		
4	R.C.C. slabs 6" thick cast at the site	"	0 10 0	36		
5	Fixing 9" C.I. pipes including carting, etc.	Cwt.	8 0 0	23		
6	Providing plug and rod including locking, etc.					
7	Cement pointing	Sqr.	4 0 0	3.23		
8	Cutting holes in orifice	Each				
	Slabs and other sundry works		As per actual measurements of work.			
	<i>Waste Weir 58.00.</i>					
1	Earthwork excavation draft approach, etc., chargeable to bund and training bank.					
2	Burnt brick in surki mortar	C.ft.	0 5 0	1,772		
3	Cement concrete slab	"	0 10 0	176		
4	Rough stone work	C.yd.	1 8 0	172		
5	Surki plastering	Sqr.	4 0 0	1.50		
6	Sundry and other items of works, rough stone grade walls in draft weir channels to prevent scours		L. S. as per actual measurement of work			
	<i>Training Bank.</i>					
1	Earthwork excavation for bank	C.yd.	0 4 0	1,196		
2	New stone work	"	1 8 0	196		
	<i>Left Sluice Channel.</i>					
1	Earthwork excavation	C.yd.	0 3 0	4,033		
2	Clearing jungle here and there					
3	Constructing rough stone work (for Kodihalla crossing)	"	1 8 0	177		
	<i>Right Channel.</i>					
1	Earthwork excavation		0 3 0	2,078		
2	Rough stone surplus weir		L. S. as per actual measurements of work			
3	Clearing jungle		Do			

Notification dated 29th April 1939.

1. Sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 2 P.M. on 13th May 1939, for constructing a bridge combined with causeway across left waste weir valley of Dharmapur Tank.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Chitaldrug Division, should be addressed to the Executive Engineer, Chitaldrug Division, in a sealed cover and superscribed as "Tender for the above work." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a deposit of Rs. 200 (in words) rupees two hundred while submitting the tender and two hundred after acceptance in cash or Government Promissory Notes or Mysore Government Bonds, duly endorsed at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 13th May 1939 at 4 P.M. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental schedule contract form, for the due fulfilment of the contract and for the execution of all items of work in accordance with the Bombay specifications 1931.

6. Failure to comply with the condition 5 above, or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of tender notification, contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Chitaldrug, on all working days between 11 A.M. and 5 P.M. and may be obtained from that officer on payment of Re. 1.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer, on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The work should be completed and handed over in a tidy condition to the Public Works Department by the end of July 1939, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 50 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(A) The contractor should at his own cost—

- (1) Provide rods, stakes, ropes and labour required in setting out the works.
- (2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
- (3) Provide mortar mills and sheds to keep materials under cover and also for workmen.
- (4) Arrange for protecting work during inclement weather.
- (5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parabs, shoring, strutting and other requisite protective appliances during the progress of the work.
- (6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
- (7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
- (8) Provide arrangements for pumping and baling of water from excavations and foundations, wherever and whenever necessary with his own pumping apparatus, including necessary leading drains, slump pits, etc.
- (9) Afford facilities to any other parties employed upon the work by the P.W.D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
- (10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by Insurance at the proper time.

Note.—(b) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

23. For lumpsum items, the details of each item of work will be recovered and paid.

24. Chamundi Brand cement alone to be used.

Abstract estimate for constructing a bridge combined with a causeway across left waste weir valley of Dharmapur Tank.

Item No.	Details of work	Unit	Rate	Quantity	Rates tendered	
					In words	In figures
1	Earthwork excavation for foundation in rocky strata and using the same for approach embankments—		Rs. a. p.			
	Soft rock ..	C.yds.	0 8 0	45		
	Hard rock ..	"	1 0 0	22		
2	Laying burnt stone jelly concrete in surki mortar combined with cement and tamping (for the levelling course) ..	C.ft.	0 4 6	286		
3	Burnt size stone masonry in mortar with bonds at every 6' apart ..	"	0 4 6	3,851		
4	Dressing the edges of corner stones and cut waters ..	S.ft.	..	..		
5	R.C.C. decking slab complete (1 : 2 : 4) (cast in situ and cured) with necessary reinforcements including centering charges ..	C.ft.	1 12 0	630		
6	(1 : 2 : 4) wearing coat of cement concrete 2" thick ..	"	0 12 0	166		
7	Providing and fixing 8" thick burnt stone slabs over the 5 feet vents ..	S.ft.	0 10 0	180		
8	(1 : 3) cement mortar pointing to the masonry racking all joints and cutting lines ..	Sqr.	3 8 0	25.53		
9	Providing and fixing two rows of gas pipes 1½" dia. hand railing in angle iron supports at every 10' apart ..	R.ft.	2 0 0	150		
10	Ornamental parapets at ends ..	"	1 8 0	48		
11	Causeway construction with up stream and down stream walls of masonry and the centre filled with rough stones broken metal and gravel, consolidation ..	"	3 0 0	100		
12	Baling out water ..	As per	actuals.			
13	Unforeseen items of work ..	As per	actuals.			

Notice dated 1st May 1939.

Sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 2 p.m. on 13th May 1939, for constructing causeway with under vents across Vedavati River on Hiriyur-Dharmapur Road.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Chitaldrug Division, should be addressed to the Executive Engineer, Chitaldrug Division, in a sealed cover and superscribed as "Tender for constructing causeway with under vents across Vedavati River on Hiriyur-Dharmapur Road." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a deposit of Rs. 200 (in words) rupees two hundred only in the first instance in cash or Government Promissory Notes or Mysore Government Bonds, duly endorsed at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 13th May 1939 at 4 p.m. The final acceptance of the tender will rest with Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental schedule contract form for the due fulfilment of the contract and for the execution of all items of work in accordance with the Bombay specifications (1931).

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreement in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of tender notification, contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Chitaldrug, on all working days, between 11 a.m. and 5 p.m. and may be obtained from that officer on payment of Re. 1. The approximate cost of the work is Rs. 17,000.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power of attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer, on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The work should be completed and handed over in a tidy condition to the Public Works Department by the end of August 1939, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 30 per day, which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind, not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note—(a) The contractor should at his own cost—

- (1) Provide rods, stakes, ropes and labour required in setting out the works.
- (2) Provide all necessary scaffolding, centering labour and appliances for hoisting.
- (3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
- (4) Arrange for protecting work during inclement weather.
- (5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
- (6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
- (7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
- (8) Provide arrangements for pumping and bailing of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus, including necessary leading drains, slump pits, etc.
- (9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract and give such persons the use of ordinary scaffolding and ladders.
- (10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

Note.—(b) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

23. Payments will be made on the actual measurements for all lumpsum provisions in the estimate

24. Chamundi Brand cement alone to be used.

Constructing High Level Causeway with under vents across Vedavati River on Hiriyur-Dharmapur Road.

No.	Items of work	Per	Rates tendered	
			In figures	In words
			Rs.	
1	Excavation in wet sand	C.yd.		
	(a) Excavation in dry sand	"		
2	Excavation in black cotton soil	"		
3	Excavation in gravelly and chattu soil	"		
4	Benching rock	Sq.ft.		
5	Concrete in surki mortar	C.ft.		
6	Rough stone boulder remmed in surki mortar	"		
7	Dressing face slabs of cut waters	Sqr.		
8	Cement mortar pointing	"		
9	Boulder filling in bottom retaining walls	"		
10	Cement concrete 1 : 2 : 4.	C.ft.		
11	Cement concrete 1 : 3 : 6	"		
12	R.C.C. decking 1 : 2 : 4 with suitable reinforcement and centering, etc.	"		
13	Forming temporary road	As per actuals		
14	Baling out water	"		

S. RAMASWAMY,
Executive Engineer.